

BRUHAT BANGALORE MAHANAGARA PALIKE


BBMP/2018-19/OW/WORK_INDENT31170

APPROVED SCHEDULE - B

EE TP/BBMP/E-PMT/03/2018-19, Date: 01.08.2018

Improvements to drains of cross road of Hoodi Muneshwara layout in ward 07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				HEMADRI REDDY ()	
				In Figures	In Words
1	266.93	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per	Cum	79.71	Rupees Seventy Nine and Seventy One Paise Only
2	55.31	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification	Cum	4731.33	Rupees Four Thousand Seven Hundred Thirty One and Thirty Three Paise Only
3	4.75	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	58917.64	Rupees Fifty Eight Thousand Nine Hundred Seventeen and Sixty Four Paise Only
4	708	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.	Sqm	355.8	Rupees Three Hundred Fifty Five and Eighty Paise Only
5	86.29	KSRB 4.2.2: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications.	Cum	5843.44	Rupees Five Thousand Eight Hundred Forty Three and Forty Four Paise Only
6	8.25	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications.	Cum	5289.33	Rupees Five Thousand Two Hundred Eighty Nine and Thirty Three Paise Only
7	221.25	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompactd cost of all materials labour curing complete as per	Sqm	1925.91	Rupees One Thousand Nine Hundred Twenty Five and Ninety One Paise Only
8	10	Providing and fixing MS Grating 260x260 mm	Nos	86.51	Rupees Eighty Six and Fifty One Paise Only
9	266.93	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification	Cum	97.21	Rupees Ninety Seven and Twenty One Paise Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
22/10